

HASSAN DIVISION.

The 11th May 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 31st May 1898, for constructing a bridge across the Codi hulla, of Harnhalli tank on Dudda-Arsikere road, Arsikere taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. & 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a bridge across the Codi hulla of Harnhalli tank, on Dudda-Arsikere road, Arsikere taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

<i>Items of work.</i>	<i>Per.</i>	<i>Rate.</i>	<i>Quantity.</i>
Earthwork excavation ordinary soil ..	C. yd.		329
Do hard soil ..	"		329
Burnt stone in mortar ..	C. ft.		11,209
Do parapets ..	"		613
Archwork ..	"		1,907
Coping slabs nicely dressed ..	"		261
Pointing in mortar ..	Sqr.		39.46
Earthwork filling ..	C. yds.		200
Metalling ..	C. yd.		16
Baling water ..	L. S.		Rs.
Guard stones dressed nicely ..	Each.		4
Drainage pipes ..	L. S.		Rs.
Centerings ..	L. S.		Rs.
Total....			
<i>Diversion.</i>			
Earthwork cutting ..	C. yds.		954
Do filling on bank ..	C. yd.		2,300
Forming road ..	S. yd.		2,000
Metalling ..	C. yd.		557
Gravelling over ..	"		696
Turfing bank slopes ..	L. S.		Rs.

A. S. NAGAVKAR, *Exec. Engineer.*

FRENCH ROCKS SUB-DIVISION.

Notice, dated 18th May 1898.

Wanted a temporary Assistant Draftsman on Rs. 25 per mensem for the French Rocks division, French Rocks. A passed candidate from the Madras Civil Engineering College, in the Drawing Branch will be preferred, and applications with copies of testimonials will be received by the undersigned up to 30th June 1898.

D. SITARAMA RAO, *Executive Engineer.*